



*Agenda for 193<sup>rd</sup> meeting of  
Municipal Corporation Chandigarh*

*Date : 24.05.2013*

*Time : 11 .00 a.m.*

*Venue : Assembly Hall*

**Municipal Corporation**  
**New Deluxe Building, Sector -17E,**  
*Chandigarh – 160017*

## **AGENDA ITEM NO. 193.1**

**Subject: Confirmation of the minutes of 192<sup>nd</sup> meeting of the General House held on 30.04.2013  
at 11.00 a.m. in the Assembly Hall of the Municipal Corporation, Chandigarh.**

## **AGENDA ITEM NO. 193.2**

### **Question/Answer**

**Question by Maj. (Retd.) D.S. Sandhu, Councillor regarding the tenure of Sub Divisional Engineer and equivalents in the various departments of Municipal Corporation.**

## **AGENDA ITEM NO. 193.3**

**Subject: Revised rough cost estimate for widening and carpeting of V-6 road in Sector 40-B, Chandigarh.**

**(Amount Rs. 86.79 lacs)**

The work of widening of V-6 road in Sector 40-B, Chandigarh amounting to Rs.69.76 lacs was administratively approved vide Chief Engineer, M.C. office Order No. 182 dated 07.06.2010. The work of widening was undertaken in the year 2011. Since the estimate was framed in the year 2010 and the rates of material and labour had been increased. The works against which estimate was administratively approved have to be executed in two parts i.e. up to surface dressing and recarpetting of existing road and widened area. The work of carpeting allotted to the agency could not start the work so that the earnest money has been forfeited and allotment of the work was cancelled and it is necessitate to revise the estimate so that remaining work may be carried out to facilitate the residents.

Accordingly, Revised rough cost estimate for widening and carpeting of V-6 road, Sector 40-B, Chandigarh amounting to **Rs. 86.79 lacs** has been prepared.

The following scope of the work has been taken in the estimate.

1. Dismantling of existing old kerbs and channels.
2. Dismantling of existing paver blocks.
3. Earth work in excavation.
4. Deduct of disposed soil
5. Carriage of earth
6. Providing and laying spreading and compacted stone aggregate 63 mm to 45 mm and 22.4 to 53mm
7. Fixing of old kerbs and channels.
8. Providing and fixing new kerbs and channels.
9. Providing and laying surface dressing.
10. Dismantling of existing cement concrete flooring.
11. Preparation of sub grade.
12. Providing and applying tack coat.
13. Providing and laying 25 mm thick SDBC.

It is certified that scope of work taken in this estimate has not earlier included in any of the estimate.

The expenditure on this work will be charged under Head “**4217 (P) Improvement of Road Parking Places and Infrastructure Facilities.**” The budget estimate, budget allocation, amount of already approved estimate and expenditure under this head for Roads Division No.3 is as under:-

i.	Budget Allocation for the year 2013-14	Rs.1100.00 lacs
ii.	Total amount of spillover works approved upto 31.03.2013	Rs.3347.33 lacs
iii.	Total amount of estimates sanctioned after 01.04.2013	Rs.95.98 lacs
iv.	Total of Sr. No. ii & iii	Rs.3443.31 lacs
v.	Expenditure incurred during current financial year.	Rs.594.00 lacs

The matter is placed before the General House of Municipal Corporation, Chandigarh for consideration and decision please.

**S.E.(B&R), M.C.**

**E.E.R-3**

## **AGENDA ITEM NO. 193.4**

**Subject: Rough cost estimate for providing and laying tack coat and 25 mm thick SDBC in Parking front of SCO 1 to 44 and back side parking SCO 17-44, Sector 7-C, along Madhya Marg, Chandigarh.**

**(Amount Rs. 55.66 lacs)**

The road parking in front of SCO 1 to 44 and back side parking SCO 17-44, Sector 7-C, Chandigarh was previously recarpetted during the month of March, 2008 and the condition of the road is very poor and is due for recarpetting as per prevailing policy of Municipal Corporation, Chandigarh i.e. the roads are recarpetted after a gap of five years.

Accordingly, Revised Rough Cost Estimate for providing and laying tack coat and 25 mm thick SDBC in Parking front of SCO 1 to 44 and back side parking SCO 17-44, Sector 7-C, along Madhya Marg, Chandigarh, amounting to **Rs. 55.66 lacs** has been prepared.

The following scope of the work has been taken in the estimate.

1. Providing and applying tack coat @ 3.00 kg/sqm and 2.50 kg/sqm.
2. Providing and laying 50 mm thick B.M. and 25 mm thick SDBC.

It is certified that scope of work taken in this estimate has not earlier included in any of the estimate.

The expenditure on this work will be charged under Head “**Improvement of Road Parking Places and Information Facilities.**” The budget estimate, budget allocation, amount of already approved estimate and expenditure under this head for Roads Division No.3 is as under:-

i.	Budget Allocation for the year 2013-14	Rs.1100.00 lacs
ii.	Total amount of spillover works approved upto 31.03.2013	Rs.3347.33 lacs
iii.	Total amount of estimates sanctioned after 01.04.2013	Rs.95.98 lacs
iv.	Total of Sr. No. ii & iii	Rs.3443.31 lacs
v.	Expenditure incurred during current financial year.	Rs.594.00 lacs

The matter is placed before the General House of Municipal Corporation, Chandigarh for consideration and decision please.

**S.E.(B&R), M.C.**

**E.E.R-3**

## **AGENDA ITEM NO. 193.5**

**Subject: Rough cost estimate for recarpeting of V-3 road Sector 35 & 43 along with cycle track Chandigarh.**

**(Amount: Rs. 65.41 Lac)**

The inspection of V-3 road was carried out by the Executive Engineer Road-1 and Sub Divisional Engineer, Roads Sub Division No.10, M.C.Chandigarh. It has been observed that lot of pot holes and depression/road cut, cracks have been developed on the road surface and therefore needs recarpeting. This road was last carpeted during the year March/2008 and due for carpeting as per the policy of M.C.

Accordingly, this rough cost estimate for providing and laying 40mm thick bituminous concrete on V-3 road and 25mm thick SDBC on cycle track along V-3 road, amounting to Rs.65.41 lac has been prepared.

The following scope of work has been taken in the estimate.

1. P/A tack coat 3kg/10sqm.
2. P/L 25mm thick SDBC.
3. P/L 40mm thick bituminous concrete.

It is certified that the scope of work taken in the estimate has not earlier included in any of the estimate.

The expenditure on this work will be charged under Head "Improvement of road parking places & Infrastructure facilities". The budget estimate, budget allocation, amount of already approved estimate and expenditure under this Head for Roads Division No.1. is as under:



i)	Budget Allocation	:	Rs. 1200.00 lacs.
ii)	Total amount of spillover works approved upto 31.03.2013.	:	Rs. 495.84 lacs.
iii)	Total Amount of estimates sanctioned after 01.04.2013.	:	Rs. 500.37 lacs.
iv)	Total of Sr. No. ii & iii	:	Rs. 996.21 lacs.
v)	Expenditure incurred during current financial year.	:	Rs. 246.34 lacs

The matter is placed before the General House of the Municipal Corporation, Chandigarh for consideration and approval please.

**S.E.(B&R), M.C.**

**E.E.Roads Divn. No.1, M.C.**

## **AGENDA ITEM NO. 193.6**

**Subject: Revised Rough Cost Estimate for construction of Mini Bus Stand at Village Maloya, Chandigarh.**

**(Amount Rs. 49.80 lacs)**

The above said rough cost estimate was approved amounting to Rs. 49.80 lacs vide CMC office order No. 308 dated 28.10.2011. Accordingly, the work was allotted to M/s Sulej Constn.Ltd. after calling tenders eight times but the work was not executed by the agency and contract was rescinded by forfeiting earnest money. Thereafter, tenders were recalled five times and two tenders were received 5<sup>th</sup> time but this time rates were high beyond the estimate and tenders has been rejected and ordered to recast the estimate by the C.E.M.C., Chandigarh these roads were last carpeted during the year 5/2006 and are due for recarpetting in 05/2011.

Accordingly, Revised Rough Cost Estimate for construction of Mini Bus Stand at Village Maloya, Chandigarh amounting to **Rs. 49.80 lacs** has been prepared.

The following scope of the work has been taken in the estimate.

1. Earth work in excavation by mechanical means.
2. Deduct for disposed soil not leveled and neatly dressed.
3. Carriage of earth by mechanical transport.
4. Preparation of sub grade.
5. Providing and laying GSB.
6. P/L the stone aggregate of 63-45mm.
7. P/L the stone aggregate of 53.22.4mm.
8. Providing and laying in position cement concrete 1:8:16
9. Supplying and filling in plinth with Jamuna sand
10. Half brick masonry with F.P.S. brick
11. 15mm cement plaster
12. P/L surface dressing as wearing coarse etc.

It is certified that scope of work taken in this estimate has not earlier included in any of the estimate.

The expenditure on this work will be charged under Head “**4217 (P) Urban Development.**”

The budget estimate, budget allocation, amount of already approved estimate and expenditure under this head for Roads Division No.3 is as under:-

i.	Budget Allocation for the year 2013-14	Rs.1100.00 lacs
ii.	Total amount of spillover works approved upto 31.03.2013	
iii.	Total amount of estimates sanctioned after 01.04.2013	-
iv.	Total of Sr. No. ii & iii	
v.	Expenditure incurred during current financial year.	

The matter is placed before the General House of Municipal Corporation, Chandigarh for consideration and decision please.

**S.E.(B&R), M.C.**

**E.E.R-3**